
EXHIBIT 6




PLANTING LEGEND

TREES		QTS. SCIENTIFIC NAME / COMMON NAME
(7)		CERCIDIPHYLLUM JAPONICUM / KATSURA TREE 1.5° CAL. B&B. WELL BRANCHED, LIMBED TO 6°
	{:}	CERCIS CANADENSIS / EASTERN REDBUD 1.5° CAL. B&B, WELL BRANCHED, LIMBED TO 6°
SHRUBS		
	\otimes	ABELIA X GRANDIFLORA "FRANCIS MASON" - FRANCIS MASON GLOSSY ABELIA 5 GAL CONT., FULL PLANTS, 4" O.C.
	0	ACER CIRCINATUM "PACIFIC FIRE" - PACIFIC FIRE VINE MAPLE 6" HIGH, B&B, WELL BRANCHED, 3 STEMS MIN. AT BASE
	(3)	AZALEA X 'KAREN / KAREN AZALEA 5 GAL CONT., FULL PLANTS, 4' O.C.
	8	BERBERIS THUNBERGII 'ATROPURPUREA NANA' / CRIMSON PYGNY JAPANESE BARBERRY 5 GAL. CONT., FULL PLANTS, 3' O.C.
	0	BUXUS SEMPERVIRENS 'GRAHAM BLANDY' / GRAHAM BLANDY BOXWOOD 6' HIGH, B&B, FULL TREES, WELL BRANCHED TO GROUND
	9	CORNUS SERICEA 'KELSEY! / KELSEY DOGWOOD 5 GAL, CONT., FULL PLANTS, 3' O.C.
	0	NANDINA DOMESTICA 'GULF STREAM' / GULF STREAM FALSE BAMBOO 5 GAL. CONT., FULL PLANTS, 3' O.C.
GROUNDO	COVER	3 3 3 3 4 3 5 3 4 3 5 4 5 4 5 5 4 5 4 5

GROUNDCOVER

F177 -	1 GAL CONT., FULL PLANTS, 24" O.C.
WWA -	MAHONIA REPENS / CREEPING MAHONIA 1 GAL. CONT., FULL PLANTS, 24° O.C.

POINT OF CONNECTION FOR IRRIGATION SYSTEM



NOTES

- ALL CONSTRUCTION SHALL BE PERFORMED IN ACCORDANCE WITH CURRENT CITY OF CAMAS STANDARDS AND THE WASHINGTON STATE BUILDING CODE.
- INSTALL EROSION CONTROL SYSTEMS IN ACCORDANCE WITH CITY CAMAS STANDARDS PRIOR TO SITE WORK AND LANDSCAPE INSTALLATION
- MARK AND PROTECT ALL UTILITIES, SITE FEATURES AND VEGETATION TO REMAIN IN PLACE.
- CONTRACTOR SHALL PROVIDE TOPSOIL, SOIL AMENDMENTS, AND EROSION CONTROL.
- 5. CONTRACTOR SHALL SUBMIT CERTIFIED TOPSOIL ANALYSIS REPORT FOR
- CONTRACTOR IS RESPONSIBLE FOR ANY AMENDMENTS TO SOIL PH FERTILITY AND/OR DRAINAGE CONDITIONS NECESSARY TO ENSURE PROPER GROWING CONDITIONS FOR PROPOSED PLANTINGS.
- ALL PLANTS SHALL BE INSTALLED ACCORDING TO AMERICAN STANDAR FOR NURSERY STOCK (ANSI 280.1) AS WELL AS DETAIL DRAWINGS AND SPECIFICATIONS.
- ALL PLANTS SHALL BE IRRIGATED BY A FULLY AUTOMATED, PERMANE IRRIGATION SYSTEM UNLESS OTHERWISE NOTED.
- CONTRACTOR SHALL INSTALL RAIN SENSORS AS PER MANUFACTURE'S INSTRUCTIONS AND RECOMMENDATIONS. VERIFY THE LOCATION WITH THE OWNER PRIOR TO INSTALLATION.
- 10. CONTRACTOR SHALL DESIGN THE IRRIGATION SYSTEM AND PROVID
- PRIOR TO FINAL ACCEPTANCE, CONTRACTOR SHALL PROVIDE OWNER WITH AS-BUILT PLANS OF THE INSTALLATION, COPIES OF ALL OPERATIO MANUALS AND WARRANTY DOCUMENTS.
- ALL NEW PLANTS IN LANDSCAPE AREAS SHALL BE WARRANTED FOR A PERIOD OF ONE YEAR FROM THE DATE OF FINAL ACCEPTANCE.



