

CITY OFFICIALS

SCOTT HIGGINS

MAYOR

MELISSA SMITH

CITY COUNCIL

PETE CAPELL

CITY ADMINISTRATOR

GREG ANDERSON

LINDA DIETZMAN

DON CHANEY

JAMES CAROTHERS

CITY ENGINEER

SHANNON TURK

TIM HAZEN

STEVE WALL

PUBLIC WORKS DIRECTOR

STEVE HOGAN

## City of Camas, Washington

# WRG TRAIL **OVERLOOK TERRACE**

#### PROJECT INFORMATION

OWNER:

CITY OF CAMAS 616 NE 4TH AVENUE CAMAS, WA 98607

ANITA ASHTON, PROJECT ENGINEEER

(360) 817-7231

LANDSCAPE ARCHITECT:

DAVID HAYNES OTAK, INC.

700 WASHINGTON STREET

SUITE 401 VANCOUVER, WA 98660

(360) 737 - 9613

SURVEYOR:

808 SW THIRD AVENUE, SUITE 300 PORTLAND, OR 97204 (503) 287-6825

### SHEET INDEX

L1.0 L1.1 L2.1 L2.2 L2.3 COVER SITE PLAN DETAIL PLAN SECTION DETAIL SITE DEVELOPMENT DETAILS

\*WILLIAMS PIPELINE CONTACT shall have a representative on site during all construction activities near the existing pipeline easement. Contact: GARY STICKNEY 360-608-9886.



STATUS

CONSTRUCTION
AS-BUILT

DRAFT

CITY OF CAMAS 9/11/15 DATE



CAMAS DRAWING NUMBER

otak

L1.0 CAMAS CATALOG NUMBER

HanmiGlobal Partne 700 Washington Street Suite 401 Vancouver, WA 98660 Phone: (360) 737-9613 FAX: (360) 737-9651

616 NE 4TH AVENUE CAMAS, WA 98607 PH:(360) 834-3451 TERRACE

800-424-5555

COVER

PUBLIC WORKS ENGINEERING DEPARTMENT OVERLOOK TRAIL WRG

CAMAS PROJECT NUMBER

P-893

1 of 5


XREF LIST Ltscale: 20 Resolved C700Bx231

C700Bx230 L700BX230 L700BX701 GIS-taxlots C700BX232 L17051x430 Unresolved \$13700B190

#### **GRADING NOTES:**


- ALL GRADING SHALL CONFORM TO THE 2014 EDITION OF THE WSDOT STANDARD SPECIFICATIONS FOR ROAD, BRIDGE AND MUNICIPAL CONSTRUCTION AND THE CITY OF CAMAS DESIGN STANDARDS
- 2. THE LIMITS OF CLEARING SHALL BE FLAGGED PRIOR TO CLEARING AND GRUBBING OF THE SITE.
- 3. ANY EXISTING TREES TO REMAIN WITHIN THE CLEARING LIMITS SHALL BE MARKED AND PROTECTED FROM DAMAGE.
- PRIOR TO ANY FILL PLACEMENT, ALL AREAS WHICH WILL RECEIVE STRUCTURAL FILL SHALL BE EXCAVATED TO FIRM, NON-ORGANIC, UNDISTURBED NATIVE GROUND. THE STRIPPED AREAS SHALL BE OBSERVED AND ACCEPTED BY THE GEOTECHNICAL ENGINEER AND THE CITY OF CAMAS INCREMENTS.
- 5. ALL RIGHT-OF-WAY FILLS SHALL MEET 95% OF AASHTO T-180 COMPACTION.
- FILLS SHALL BE INSTALLED IN VERTICAL LIFTS NOT EXCEEDING 8 INCHES IN THICKNESS AND SHALL BE COMPACTED AS PREVIOUSLY NOTED.
- FILLS PLACED ON SLOPES EXCEEDING 5H:IV SHALL BE KEYED AND BENCHED, GEOTECHNICAL APPROVAL REQUIRED PRIOR TO ANY FILL PLACEMENT.
- ALL SURFACES SHALL BE GRADED SMOOTH AND BE FREE OF IRREGULARITIES THAT MIGHT ACCUMULATE SURFACE WATER.
- 9. ALL CUT AND FILL SLOPES SHALL NOT EXCEED 2:1 SLOPES.
- 10. ANY EXCESS MATERIAL NOT REQUIRED TO MEET THE GRADES SHOWN ON THE PLANS SHALL BE HAULED FROM THE SITE TO A CONTRACTOR PROVIDED WASTE SITE. IF WASTE SITE IS WITHIN CITY LIMITS, A GRADING PERMIT MAY BE REQUIRED.
- 11. ALL EXPOSED AND UNWORKED SOILS SHALL BE STABILIZED BY SUITABLE APPLICATION OF
- ALL SURFACES REQUIRING VEGETATION SHALL BE ROUGHENED PRIOR TO SEEDING (I.E. WHEEL TRACKED PERPENDICULAR TO SURFACE FLOW TO REDUCE EROSION AND HELP VEGETATION).
- 13. FINAL GEOTECHNICAL SUMMARY REPORT, INCLUDING ALL COMPACTION TESTING RESULTS, SHALL BE SUBMITTED UPON COMPLETION OF SITE GRADING WORK.

DOES NOT APPLY



#### EROSION CONTROL NOTES

- 1. ONLY CONSTRUCTION VEHICLES ARE ALLOWED OFF-STREET AND MUST BE UTILIZED ONLY ON GRAVEL CONSTRUCTION ACCESS AREAS
- 2. WORKERS' PERSONAL VEHICLES SHALL BE PARKED ON ADJACENT STREETS OR OTHER APPROVED AREAS.
- 3. ALL UNWORKED AND EXPOSED SOILS MUST BE STABILIZED BY SEEDING, COVERING, OR MULCHING FROM THE CURB LINE TO AT LEAST TEN FEET FROM THE BUILDING ENVELOPE.
- GRAVEL DRIVES USED AS SITE ENTRANCES SHALL BE CONSTRUCTED OF MINIMUM TWO-INCH DIAMETER GRAVEL AND NO FINER MATERIALS ARE ALLOWED.
- 5. CONSTRUCTION MATERIALS SUCH AS LUMBER SHALL BE DELIVERED AND STORED ON DESIGNATED LOCATIONS WHICH ARE STABILIZED AND PROTECTED FROM EROSION.
- 6. EROSION CONTROL MEASURES SHALL BE REVIEWED AND INSPECTED AT THE END OF EACH DAY. IN NONWORK PERIODS, INSPECTIONS SHALL TAKE PLACE AFTER EACH RAINFALL OR AT LEAST ONCE A WEEK, WHICHEVER IS MORE FREQUENT. NEEDED CORRECTIONS SHALL BE MADE IMMEDIATELY.
- 7. SEE SHEET L2.3 FOR ADDITIONAL EROSION CONTROL NOTES AND DETAILS.





www.otak.com

700 Washington Street Suite 401 Vancouver, WA 98660 Phone: (360) 737-9613 FAX: (360) 737-9651

CAMAS PROJECT NUMBER P-893 STATUS DRAFT 2 of 5 X CONSTRUCTION

CAMAS DRAWING NUMBER

424-

800

45

TERRA(

90K

귒

OVE

R

0

4H 4 ₩ 83.


PLAN

SITE

L1.1

AS-BUILT


CAMAS CATALOG NUMBER





HanmiGlobal Partner 700 Washington Street Suite 401 Vancouver, WA 98660 Phone: (360) 737-9613 FAX: (360) 737-9551 www.otak.com


L2.1 CAMAS CATALOG NUMBER



XREF\_LIST Ltscale: 20 C7008x231 L700BX230 L700BX70 GIS-taxlots C700BX232 117051v430 Unresolved \$13700B190 GIS-2ftcont 17051~-ske Aerial 1

#### EROSION/SEDIMENT CONTROL NOTES:

- THE EROSION/SEDIMENT CONTROL (ESC) PLAN AND STORMWATER POLLUTION PREVENTION PLAN (SWPPP) IS TO BE UTILIZED AS A GUIDE TO CONTROL THE TRANSPORT OF LOOSE SOILS TO THE PROPERTY OUTSIDE OF THE CONSTRUCTION AREA AND AROUND THE CONSTRUCTION SITE. THE ESC MEASURES SHALL BE UPGRADED AS NEEDED FOR UNEXPECTED STORM EVENTS AND TO ENSURE THAT SEDIMENT AND SEDIMENT LADEN
- 2. THE IMPLEMENTATION OF THE ESC PLANS AND THE CONSTRUCTION, MAINTENANCE, REPLACEMENT AND UPGRADING OF THE ESC MEASURES IS THE RESPONSIBILITY OF THE CONTRACTOR UNTIL ALL CONSTRUCTION IS COMPLETED AND APPROVED AND PERMANENT VEGETATION/LANDSCAPING IS ESTABLISHED.
- 3. THE CONTRACTORS SHALL BE RESPONSIBLE TO FAMILIARIZE THEMSELVES WITH THE 2005 EDITION OF THE STORMWATER MANAGEMENT MANUAL FOR WESTERN WASHINGTON, VOL. II AND THE CITY OF CAMAS MUNICIPAL CODE 14.06 (2011).
- 4. ALL EROSION/SEDIMENT CONTROL MEASURES SHALL BE IN PLACE AND IN WORKING CONDITION PRIOR TO DISTURBING AND EXPOSING ANY SOIL SURFACES (I.E. CONSTRUCTION ENTRANCES, FILTER FABRIC SEDIMENT BARRIERS, AND SEDIMENTATION TRAPS) AND MAINTAINED FOR THE DURATION OF THE PROJECT. TRAPPED SEDIMENT IN EXCESS OF 1 FOOT SHALL BE REMOYED OR STABILIZED ON—SITE. DISTURBED SOIL AREAS RESULTING FROM VEGETATION REMOVAL SHALL BE PERMANENTLY STABILIZED. ADDITIONAL MEASURES MAY BE REQUIRED TO ENSURE THAT ALL PAVED AREAS ARE KEPT CLEAN FOR THE DURATION OF THE PROJECT.
- 5. TO MINIMIZE EROSION AND SEDIMENTATION TRANSPORTATION, EARTHWORK SHALL NOT BE PERFORMED WHILE SOILS ARE IN AN UNSTABLE STATE DUE TO PRECIPITATION.
- 6. THE CONTRACTOR SHALL BE RESPONSIBLE TO HAVE CLEARING LIMITS AND/OR ANY EASEMENTS, SENSITIVE OR CRITICAL AREAS, AND THEIR BUFFERS, TREES, AND DRAINAGE COURSES FLAGGED PRIOR TO CONSTRUCTION. DURING THE CONSTRUCTION PERIOD, NO DISTURBANCE BEYOND THE FLAGGED CLEARING LIMITS SHALL BE PERMITTED. FLAGGING LIMITS ARE TO BE MAINTAINED BY THE CONTRACTOR FOR THE DURATION OF CONSTRUCTION.



- 7. REMOVE ONLY THOSE TREES AND SHRUBS THAT NEED TO BE REMOVED FOR THE CONSTRUCTION OF ROADS, SIDEWALKS, UTILITIES, AND STORMWATER FACILITIES.
- B. ALL EXISTING AND NEWLY CONSTRUCTED ROAD CATCH BASINS AND CURB INLETS AFFECTED BY CONSTRUCTION SHALL BE PROTECTED AGAINST SEDIMENT DEPOSITS. AT NO TIME SHALL MORE THAN ONE FOOT OF SEDIMENT BE ALLOWED TO ACCUMULATE WITHIN A TRAPPED CATCH BASIN. ALL CATCH BASINS AND CONVEYANCE LINES SHALL BE CLEANED PRIOR TO PAVING. THE CLEANING OPERATION SHALL NOT FLUSH SEDIMENT LADEN WATER INTO THE
- 9. ALL POLLUTANTS THAT OCCUR ON—SITE DURING CONSTRUCTION SHALL BE HANDLED AND DISPOSED OF IN A MANNER THAT DOES NOT CAUSE CONTAMINATION OF STORMWATER SYSTEM.
- 10. ALL DISTURBED SOIL SURFACES ARE TO BE STABILIZED BY A SUITABLE APPLICATION OF "BEST MANAGEMENT PRACTICES" (BMP'S). DURING THE PERIOD OF OCTOBER 1 THROUGH JULY 5 DISTURBED SOILS MAY REMAIN UNSTABILIZED FOR UP TO TWO DAYS WHEN NOT BEING WORKED. FROM JULY 5 THROUGH OCTOBER 1, DISTURBED SOILS MAY REMAIN UNSTABILIZED FOR UP TO 7 DAYS WHEN NOT BEING WORKED. STABILIZATION OF DISTURBED SOIL AREAS MAY CONSIST OF HYDROSEEDING, HAND—SEEDING AND MULCHING, PLACEMENT OF EROSION CONTROL BLANKETS OR PLASTIC. ALL SEEDED AREAS ARE TO BE FERTILIZED, WATERED, AND MAINTAINED TO ENSURE THAT THE GROWTH OF VEGETATION OCCURS AS SOON AS POSSIBLE.
- 11. ALL TEMPORARY SEDIMENT AND EROSION CONTROL BMP'S SHALL BE REMOVED WITHIN 30 DAYS AFTER FINAL SITE STABILIZATION IS ACHIEVED OR AFTER THE TEMPORARY BMP'S ARE NO LONGER NEEDED.
- 12. THE CONTRACTOR SHALL BE RESPONSIBLE FOR POLICING THE JOB SITE DAILY AND MAINTAINING THE FROSION/SEDIMENT CONTROL MEASURES THROUGHOUT THE CONTRACTOR SHALL BE RESPONSIBLE FOR POLICING THE JOB SITE DAILY AND MAINTAINING THE EROSION/SEDIMENT CONTROL MEASURES THROUGHOUT ALL PHASES OF CONSTRUCTION. AN INSPECTION LOG SHALL BE KEPT AND MAD AVAILABLE TO THE CITY OF CAMAS. THE POLICING AND MAINTENANCE SHALL INCLUDE, BUT NOT BE LIMITED TO:

  - VERIFYING THAT ALL AREAS ARE GRADED SUCH THAT ALL RUNOFF IS DIRECTED TO A SEDIMENTATION DEVICE BEFORE DISCHARGE TO SURFACE.

  - REMOVAL OF TRAPPED SILT AT SILT BARRIERS, SILT TRAPS, OR POINTS OF ACCUMULATION.

  - ADDITIONAL PROTECTIVE MEASURES DUE TO JOB SITE OR WEATHER CONDITIONS AS REQUIRED BY THE CITY OF CAMAS.

  - WONTORNING OF VEHICLES LEAVING THE SITE TO MINIMIZE TRANSMISSION OF LOSS SOILS TO THE PUBLIC ROADWAYS.

  - VERIFY THAT ALL PROPERTIES ADJACENT TO THE PROJECT SITE ARE PROTECTED FROM SEDIMENTATION DEPOSITION. THIS MAY BE ACCOMPLISHED BY INSTALLING PERIMETER CONTROL AS SCHIMENTATION ARRIVES OF BY A COMBINATION OF

- INSTALLING PERIMETER CONTROLS SUCH AS SEDIMENTATION BARRIERS, FILTERS OR DIKES, SEDIMENTATION BASINS/TRAPS, OR BY A COMBINATION OF SUCH MEASURES.
- 13. CUT AND FILL SLOPES SHALL BE DESIGNED AND CONSTRUCTED IN A MANNER THAT WILL MINIMIZE EROSION. SLOPES SHALL BE STABILIZED IN ACCORDANCE WITH EROSION/SEDIMENT CONTROL NOTE 10.
- 14. THE ESC MEASURES ON INACTIVE SITES SHALL BE INSPECTED AND MAINTAINED A MINIMUM OF ONCE A MONTH OR WITHIN 24 HOURS FOLLOWING ANY
- 15. THE CONTRACTOR SHALL BE RESPONSIBLE FOR INSTALLING UNDERGROUND UTILITIES AS SPECIFIED BELOW:
- WHERE FEASIBLE, NO MORE THAN 500 FEET OF TRENCH SHALL BE OPEN AT ONE TIME.

   WHERE CONSISTENT WITH SAFETY AND SPACE CONSIDERATIONS, EXCAVATED MATERIAL SHALL BE PLACED ON THE UPHILL SIDE OF TRENCHES.

   TRENCH DE-WATER DEVICES SHALL DISCHARGE INTO A SEDIMENT TRAP OR SEDIMENT POND.
- 16. SUGGESTED STANDARD SEED MIXTURE FOR THOSE AREAS WHERE A TEMPORARY VEGETATIVE COVER IS REQUIRED.

TEMPORARY EROSION CONTROL MIX*			
SEED VARIETY	% WEIGHT	% PURITY	% GERMINATION
CHEWINGS OR ANNUAL BLUE GRASS	40	98	90
(FESTUCA RUBRA VAR. COMMUTATA OR	POA ANNA)		
PERÈNNIAL RYE	50 ´	98	90
(LOLIUM PERENNE)			
REDTOP OR COLONIAL BENTGRASS	5	92	85
(AGROSTIS ALBA OR AGROSTIS TENUIS)			
WHITE DUTCH CLOVER	5	98	90
(TRIEGIUIU PEDENC)			

\*APPLICATION RATE OF 120 LBS/ACRE AND COVERED WITH STRAW OR MULCH



HanmiGlobal Partner 700 Washington Street Suite 401 Vancouver, WA 98660 Phone: (360) 737-9613 FAX: (360) 737-9651 www.otak.com 2 BUSINE BEFORE

DAYS J DIG

-5555

"∾¤

the

SCALES HORIZONTAL: AS SHOW VERTICAL: CONTACTS DESIGNED BY: DESIGNED BY	AS-BUILL DAIE:		
WYACTS DI S: DI	SCALE	S	
ONTACTS	HORIZONTAL:	AS	SHOW
ONTACTS	VERTICAL:	AS	SHOW
	CONTAC	STS	
	DESIGNED BY:	HDD	
	APPROVED BY:	DLS	

4TH WA 83

or TMEN  $\overline{\simeq}$ TAILS DEPART B /ELOPMENT Z PUBLIC ENGINEERING OVE DEV TRAIL SITE

WORKS

WRG

CAMAS PROJECT NUMBER P-893

STATUS PAGE DRAFT 5 of 5 CONSTRUCTION AS-BUILT

CAMAS DRAWING NUMBER

L2.3

CAMAS CATALOG NUMBER